## Location: 9-15 (A)

## MAXIMUM BEAM/SHELF LOADS - kgs

(UNIFORMLY DISTRIBUTED)



Conduct regular inspections to check for:

- correct application and use
- loads within allowable safe limits
- accidental damage or dislodgement of structure components




REPORT ALL DAMAGE TO PERSON RESPONSIBLE FOR SITE MANAGEMENT

175 kg MAX.



REPORT ALL ACCIDENTS



- checking effects against manufacturer's technical data
- obtaining approval from supplier

175 kg MAX.

175 kg MAX.

175 kg MAX.

DO NOT CLIMB ON SHELVING OR RACKING

175 kg MAX.



REFER TO SEMA CODE OF PRACTICE



IF IN DOUBT ALWAYS CONTACT THE SUPPLIER

## **BAY LOAD - kgs**

875 kg

**Total Load On All Beams Should Not Exceed Bay Load** 

JOB REF:

DATE SUPPLIED:

NOTES:

CONTACT: TEL. NO:

THIS NOTICE SHOULD NOT BE REMOVED